

BRUHAT BANGALORE MAHANAGARA PALIKE

Dasarahalli Zone

Schedule-B

Name of works: Improvements to Roads Drains At Chikkasandra village in Ward No 12
Shettyhally Sub Division

Sl No	Description of Work	Unit	Qty	Rates	
				In Figures	In Words
1	Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work. including Conveying the excavated earth silt, debris and over burden earth etc., to lead of 0 to 5 kms distance by using private vehicle this includes the cost of loading and unloading charges etc., complete as per the direction of Engineer-in-charge of the work	Cum	2643.60	211.79	Rupees Two Hundred Eleven And Paise Seventy Nine Only
2	KSRRB M2100 -10. Plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46 cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scafolding and centering complete as per specifications MORTH Specification No. 2100 (PWD SR 2017-18 Page No.222 , Item No. 27.18)	Cum	12.60	5421.90	Rupees Five Thousand Four Hundred Twenty One And Paise Ninety Only
3	Providing laying plain / reinforced cement concrete for side Drain using M20 nominal mix concrete with OPC at 300 kgs with 20 mm and down size granite metal coarse aggregates at 0.69 cum fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., completet excluding cost of steel ae per MMORTH specification No 1500, 1700, 2200. including cost of materials, labour, HOM completet as per specificatios. wall and bottom thickness 15 cms	Cum	26.25	7070.20	Rupees Seven Thousand Seventy And Paise Twenty Only
4	KSRRB M2200-6. Supplying, fitting and placing TMT bar Fe 500 reinforcement in sub-structure complete as per drawing and Technical Specifications complete as per specificationsMORTH Specification No.1600 & 2200	Ton	1.71	72316.38	Rupees Seventy Two Thousand Three Hundred Sixteen And Paise Thirty Eight Only
5	Supplying and fixing precast reinforced concrete slab 10 cm thick of mix M20 using 20mm and downsize graded granite metal using reinforcement 10mm dia steel at 150mmc/c bothways cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials	Sqm	126.00	2208.00	Rupees Two Thousand Two Hundred Eight Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahangara Palike,
Dasarahalli Division, Bengaluru-57

Bengaluru-57

5

Providing and laying **Pre Cast Drain Cover slabs of 250mm thick for drain** in cement concrete m 20 using graded granite jelly 20 mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both side etc complete and as per drawing and directions of Engineer-in-charge of work (Data Rate enclosed)

Sqm

10.50

5241.00

Rupees Five Thousand Two
Hundred Forty One Only


EXECUTIVE ENGINEER-4
KRIIDL, BBMP DIVISION
BENGALURU-560 010


EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike,
Dasarahalli Division, Bengaluru-57